

AD-A085 292

KIMBALL (L ROBERT) AND ASSOCIATES EBENSBURG PA  
NATIONAL DAM INSPECTION PROGRAM, WASTE HOUSE RUN NUMBER 3 DAM (ETC(U)  
APR 80 R J KIMBALL

F/G 13/13  
DACV31-80-C-0000  
NL

UNCLASSIFIED

1 of 1  
AD-A085292



END  
DATE  
FILMED  
7-80  
DTIC

TC

12

ADA 085292

SUSQUEHANNA RIVER BASIN  
WASTE HOUSE RUN, SCHUYLKILL COUNTY

PENNSYLVANIA

# WASTE HOUSE RUN NO. 3 DAM

NDS ID NO. PA-684

DER ID NO. 54-26

LEVEL II

MAHANoy TOWNSHIP MUNICIPAL AUTHORITY

## PHASE I INSPECTION REPORT NATIONAL DAM INSPECTION PROGRAM

L. ROBERT KIMBALL & ASSOCIATES

DACW31-80-C-0020



DTIC  
COLLECTED  
JUN 9 1980  
C

ORIGINAL CONTAINS COLOR PLATES; ALL DDD  
REPRODUCTIONS WILL BE IN BLACK AND WHITE.

DDC FILE COPY

Prepared By  
**L. ROBERT KIMBALL & ASSOCIATES**  
CONSULTING ENGINEERS & ARCHITECTS  
EBENSBURG, PENNSYLVANIA  
15931

FOR  
**DEPARTMENT OF THE ARMY**  
**BALTIMORE DISTRICT CORPS OF ENGINEERS**  
BALTIMORE, MARYLAND  
21203

This document has been approved  
for public release and sale; its  
distribution is unlimited.

APRIL, 1980

80 6 6 039

SUSQUEHANNA RIVER BASIN  
WASTE HOUSE RUN, SCHUYLKILL COUNTY

65 National Dam Inspection Program

## WASTE HOUSE RUN NO. 3 DAM

UNDS ID Number FA-684-~~5510-1~~

DE ID Number 54-26-~~5510-1~~


Susquehanna River Basin Waste House Run

~~MALDEN TOWNSHIP MUNICIPAL AUTHORITY~~

Schuylkill County, Pennsylvania

PHASE I INSPECTION REPORT

NATIONAL DAM INSPECTION PROGRAM



11 APR 80

JUN 9 1980

R. J. Jeffrey Kimball

Prepared By

411059 L. ROBERT KIMBALL & ASSOCIATES  
CONSULTING ENGINEERS & ARCHITECTS  
EBENSBURG, PENNSYLVANIA  
15931

15 DAW 31-80-C-0020

FOR  
DEPARTMENT OF THE ARMY  
BALTIMORE DISTRICT CORPS OF ENGINEERS  
BALTIMORE, MARYLAND  
21203

APRIL, 1980

This document has been approved  
for public release and sale; its  
distribution is unlimited.

411059 all

## PREFACE

This report is prepared under guidance contained in the Recommended Guidelines for Safety Inspection of Dams, for Phase I Investigations. Copies of these guidelines may be obtained from the Office of Chief of Engineers, Washington, D.C. 20314. The purpose of a Phase I investigation is to identify expeditiously those dams which may pose hazards to human life or property. The assessment of the general condition of the dam is based upon available data and visual inspections. Detailed investigation, and analyses involving topographic mapping, subsurface investigations, testing, and detailed computational evaluations are beyond the scope of a Phase I investigation; however, the investigation is intended to identify any need for such studies.

In reviewing this report, it should be realized that the reported condition of the dam is based on observations of field conditions at the time of inspection along with data available to the inspection team. In cases where the reservoir was lowered or drained prior to inspection, such action, while improving the stability and safety of the dam, removes the normal load on the structure and may obscure certain conditions which might otherwise be detectable if inspected under the normal operating environment of the structure.

It is important to note that the condition of a dam depends on numerous and constantly changing internal and external conditions, and is evolutionary in nature. It would be incorrect to assume that the present condition of the dam will continue to represent the condition of the dam at some point in the future. Only through frequent inspections can unsafe conditions be detected and only through continued care and maintenance can these conditions be prevented or corrected.

Phase I inspections are not intended to provide detailed hydrologic and hydraulic analyses. In accordance with the established Guidelines, the spillway design flood is based on the estimated "Probable Maximum Flood" for the region (greatest reasonably possible storm runoff), or fractions thereof. The spillway design flood provides a measure of relative spillway capacity and serves as an aid in determining the need for more detailed hydrologic and hydraulic studies, considering the size of the dam, its general condition and the downstream damage potential.

Account Number

NAME

DOB

UNIT

on file

1

2

3

4

5

6

7

8

9

10

11

12

13

14

15

16

17

18

19

20

21

22

23

24

25

26

27

28

29

30

31

32

33

34

35

36

37

38

39

40

41

42

43

44

45

46

47

48

49

50

51

52

53

54

55

56

57

58

59

60

61

62

63

64

65

66

67

68

69

70

71

72

73

74

75

76

77

78

79

80

81

82

83

84

85

86

87

88

89

90

91

92

93

94

95

96

97

98

99

100

101

102

103

104

105

106

107

108

109

110

111

112

113

114

115

116

117

118

119

120

121

122

123

124

125

126

127

128

129

130

131

132

133

134

135

136

137

138

139

140

141

142

143

144

145

146

147

148

149

150

151

152

153

154

155

156

157

158

159

160

161

162

163

164

165

166

167

168

169

170

171

172

173

174

175

176

177

178

179

180

181

182

183

184

185

186

187

188

189

190

191

192

193

194

195

196

197

198

199

200

201

202

203

204

205

206

207

208

209

210

211

212

213

214

215

216

217

218

219

220

221

222

223

224

225

226

227

228

229

230

231

232

233

234

235

236

237

238

239

240

241

242

243

244

245

246

247

248

249

250

251

252

253

254

255

256

257

258

259

260

261

262

263

264

265

266

267

268

269

270

271

272

273

274

275

276

277

278

279

280

281

282

283

284

285

286

287

288

289

290

291

292

293

294

295

296

297

298

299

300

301

302

303

304

305

306

307

308

309

310

311

312

313

314

315

316

317

318

319

320

321

322

323

324

325

326

327

328

329

330

331

332

333

334

335

336

337

338

339

340

341

342

343

344

345

346

347

348

349

350

351

352

353

354

355

356

357

358

359

360

361

362

363

364

365

366

367

368

369

370

371

372

373

374

375

376

377

378

379

380

381

382

383

384

385

386

387

388

389

390

391

392

393

394

395

396

397

398

399

400

401

402

403

404

405

406

407

408

409

410

411

412

413

414

415

416

417

418

419

420

421

422

423

424

425

426

427

428

429

430

431

432

433

434

435

436

437

438

439

440

441

442

443

444

445

446

447

448

449

450

451

452

453

454

455

456

457

458

459

460

461

462

463

464

465

466

467

468

469

470

471

472

473

474

475

476

477

478

479

480

481

482

483

484

485

486

487

488

489

490

491

492

493

494

495

496

497

498

499

500

501

502

503

504

505

506

507

508

509

510

511

512

513

514

515

516

517

518

519

520

521

52

PHASE I REPORT  
NATIONAL DAM INSPECTION REPORT

NAME OF DAM	Waste House Run No. 3 Dam
STATE LOCATED	Pennsylvania
COUNTY LOCATED	Schuylkill
STREAM	Waste House Run
DATE OF INSPECTION	November 8 and 16, 1979

ASSESSMENT

The assessment of Waste House Run No. 3 Dam is based upon visual observations made at the time of inspection, interviews with the owner and hydrologic and hydraulic analyses.

Waste House Run No. 3 Dam is a high hazard-intermediate size dam. The dam is in fair condition. The spillway design flood is the PMF (Probable Maximum Flood). The spillway and reservoir are capable of controlling approximately 55% of the PMF without overtopping the embankment. Based on criteria established by the Corps of Engineers, the spillway is termed inadequate. Seepage is exiting at several locations at the toe of dam. One of these seepage areas is approximately 8 feet above the toe of dam on the upstream wall of the valve house. Significant movement of the downstream slope and walls of the valve house are in evidence and additional analyses are warranted.

The following recommendations and remedial measures should be instituted immediately.

1. The spillway control section (weir) should be repaired.
2. A detailed study, including a stability analysis, should be conducted by a registered professional engineer knowledgeable in earth dams to evaluate the seepage, movement of the walls in the valve house and possible downstream slope instability. The study should include monitoring and testing as required.
3. All brush, trees and debris should be cleared from the spillway.
4. All brush and trees should be cleared from the slopes and crest under the direction of a professional engineer knowledgeable in the design and construction of earth dams.
5. All seepage areas should be monitored on a regular basis and after periods of heavy precipitation and evaluated by a professional engineer knowledgeable in dam design and analyses.
6. Some means of upstream positive closure of the drainline should be developed in the case of emergencies.

WASTE HOUSE RUN NO. 3 DAM  
PA-684

7. The leaking valves located in the valve house should be repaired and exercised and lubricated on a regular basis.

8. A warning system should be developed to warn downstream residents of large spillway discharges or imminent failure of the dam.

9. Regular safety inspections should be conducted in accordance with provisions stipulated by the Commonwealth of Pennsylvania regarding the inspection of dams.

10. Improve the access to the dam so the dam will be accessible during periods of flooding.

SUBMITTED BY:

L. ROBERT KIMBALL & ASSOCIATES  
CONSULTING ENGINEERS AND ARCHITECTS



April 11, 1980

Date

*R. Jeffrey Kimball*  
R. Jeffrey Kimball, P.E.


APPROVED BY:

16 May 1980

Date

*James W. Peck*  
JAMES W. PECK  
Colonel, Corps of Engineers  
District Engineer

Approved for	
Noted	
Disputed	
Unsubstantiated	
Recommendation	<i>for file</i>
Remarks	
Signature	
Date	
Initials	
or	
Initials	
A	



Overview of Waste House Run No. 3 Dam.

## TABLE OF CONTENTS

	PAGE
SECTION 1 - PROJECT INFORMATION	1
1.1 General	1
1.2 Description of Project	1
1.3 Pertinent Data	2
SECTION 2 - ENGINEERING DATA	5
2.1 Design	5
2.2 Construction	5
2.3 Operation	5
2.4 Evaluation	5
SECTION 3 - VISUAL INSPECTION	6
3.1 Findings	6
3.2 Evaluation	7
SECTION 4 - OPERATIONAL PROCEDURES	8
4.1 Procedures	8
4.2 Maintenance of Dam	8
4.3 Maintenance of Operating Facilities	8
4.4 Warning System in Effect	8
4.5 Evaluation	8
SECTION 5 - HYDRAULICS AND HYDROLOGY	9
5.1 Evaluation of Features	9
5.2 Evaluation Assumptions	9
5.3 Summary of Overtopping analysis	9
5.4 Summary of Dam Breach Analysis	10
SECTION 6 - STRUCTURAL STABILITY	11
6.1 Evaluation of Structural Stability	11
SECTION 7 - ASSESSMENT AND RECOMMENDATIONS/REMEDIAL MEASURES	12
7.1 Dam Assessment	12
7.2 Recommendations/Remedial Measures	12



## APPENDICES

- APPENDIX A - CHECKLIST, VISUAL INSPECTION, PHASE I
- APPENDIX B - CHECKLIST, ENGINEERING DATA, DESIGN, CONSTRUCTION,  
OPERATION, PHASE I
- APPENDIX C - PHOTOGRAPHS
- APPENDIX D - HYDROLOGY AND HYDRAULICS
- APPENDIX E - DRAWINGS
- APPENDIX F - GEOLOGY

PHASE I  
NATIONAL DAM INSPECTION PROGRAM  
WASTE HOUSE RUN NO. 3 DAM  
NDI. I.D. NO. PA 684  
DER I.D. NO. 54-26

SECTION 1  
PROJECT INFORMATION

1.1 General.

a. Authority. The National Dam Inspection Act, Public Law 92-367, authorized the Secretary of the Army, through the Corps of Engineers, to initiate a program of inspection of dams throughout the United States.

b. Purpose. The purpose of the inspection is to determine if the dam constitutes a hazard to human life or property.

1.2 Description of Project.

a. Dam and Appurtenances. Waste House Run No. 3 Dam is an earthfill dam, 41 feet high and 1080 feet long. The crest width of the dam is 7 feet. The upstream slope is 2.5H:1V and protected with hand placed riprap. The downstream slope is 1.5H:1V and covered with stone rubble. A puddle ditch, to cutoff seepage, is carried to bedrock.

The spillway is located on the right abutment and is excavated into the hillside. The weir is 34 feet long and is trapezoidal shaped. The spillway exit channel is 280 feet long at a 2% grade. The bottom and side slopes of the spillway are protected with hand placed riprap.

The reservoir outlet is provided by a 20 inch diameter cast iron pipe which terminates in a gate house at the downstream toe of the dam. There are two valves in the gate house to regulate the flow. Water discharges from the pipe into the old creek bed and flows into Waste House Run No. 2 Dam which is located 3000 feet downstream of Waste House Run No. 3 Dam. The pipe is carried through the dam on a masonry wall resting upon the underlying bedrock and encased in concrete. Two cutoffs are provided along the pipe.

b. Location. The dam is located on Waste House Run, approximately 3 1/2 miles northeast of Shenandoah, Schuylkill, Pennsylvania. Waste House Run No. 3 Dam can be located on the Shenandoah, U.S.G.S. 7.5 minute quadrangle.

c. Size Classification. Waste House Dam No. 3 is an intermediate size dam (41 feet high, 239 acre-feet).

d. Hazard Classification. Waste House Run No. 3 Dam is a high hazard dam. Downstream conditions indicate that loss of more than a few lives is probable should the structure fail. Another reservoir, Waste House Run No. 2 Dam, is located 3000 feet downstream of Waste House Run No. 3 Dam. Approximately 2000 feet downstream of Waste House Run No. 2 Dam is a mine complex and several dwellings.

e. Ownership. Waste House Run No. 3 Dam is owned by the Mahanoy Township Authority. Correspondence should be addressed to:

George Palmer, Manager  
Mahanoy Township Authority  
46 North Main Street  
Mahanoy City, PA 17948  
(717) 773-0650

f. Purpose of Dam. Waste House Run No. 3 Dam is used for water supply.

g. Design and Construction History. Waste House Run No. 3 Dam was designed by George S. Clemens, an engineer for the Philadelphia & Reading Coal and Iron Company. Construction began in June, 1901 and finished in October, 1902, under the supervision of John H. Pollard, an engineer for the P & R Coal and Iron Company. The embankment was constructed of a mixture of clay and gravel which was laid in six inch layers, sprinkled and rolled with a grooved roller. Several springs appeared during the construction of the foundation. One of these springs was located in the puddle ditch and was controlled by means of a french drain, covered with concrete, and drained by a 6 inch pipe encased in concrete and outletted below the toe of dam. Another spring developed on the west side near the upstream toe which was boxed in concrete and drained by a 6 inch pipe encased in concrete to the sluiceway at the lower end at the outlet pipe.

h. Normal Operating Procedures. The reservoir level is maintained at the spillway crest elevation. The outlet pipe has remained closed for several years. The excess inflow is discharged through the spillway.

### 1.3 Pertinent Data.

- |  |                   |
|--|-------------------|
| a. <u>Drainage Area.</u>               | 0.37 square miles |
| b. <u>Discharge at Dam Site (cfs).</u> |                   |
| Maximum known flood at dam site        | Unknown           |
| Drainline capacity at normal pool      | Unknown           |
| Spillway capacity at top of dam        | 490               |

c. Elevation (U.S.G.S. Datum) (feet). - Field survey based on pool elevation 1713.0 shown on U.S.G.S. 7.5 minute quadrangle.

Top of dam - low point	1715.7
Top of dam - design height	Unknown
Normal pool	1713.0
Spillway crest	1713.0
Streambed at centerline of dam	1674.8
Toe of dam	1674.8

d. Reservoir (feet).

Length of maximum pool	850
Length of normal pool	800

e. Storage (acre-feet).

Normal pool	193
Top of dam	239

f. Reservoir Surface (acres).

Top of dam	20
Normal pool	15.2
Spillway crest	15.2

g. Dam.

Type	Earthfill
Length	1080'
Height	41'
Top width	7'
Side slopes - upstream	2.5H:1V
- downstream	1.5H:1V
Zoning	Yes
Impervious core	Puddle core
Cutoff	None
Grout curtain	None

h. Reservoir Drain.

Type	20" CIP
Length	Approximately 240'
Closure	Valve at toe
Access	Downstream end
Regulating facilities	Valve at toe

i. Spillway.

Type  
Bottom width  
Crest elevation  
Upstream channel  
Downstream channel

Trapezoidal  
34'  
1713'  
Lake  
280' long trapezoidal  
channel

## SECTION 2 ENGINEERING DATA

2.1 Design. No data was provided by the owner pertaining to the design of the dam. Some data was available from the Commonwealth of Pennsylvania, Department of Environmental Resources pertaining to construction of the dam, inspection reports, photographs and correspondence.

2.2 Construction. A minimum amount of construction information was available from a report prepared in 1914 and contained in the Commonwealth of Pennsylvania files. (See section 1.2g).

2.3 Operation. No operating records are maintained.

2.4 Evaluation.

a. Availability. No engineering data was provided by the owner. Some background data was provided by PennDER. A representative of the owner accompanied the inspection team to answer questions on any operations or maintenance of the dam.

b. Adequacy. The information available is not sufficient to conduct a detailed engineering study. The Phase I report is completed based upon data obtained from the PennDER files, visual inspection and hydrologic analyses, only.

SECTION 3  
VISUAL INSPECTION

3.1 Findings.

a. General. The onsite inspection of Waste House Run No. 3 Dam was conducted by personnel of L. Robert Kimball and Associates on November 8 and 16, 1979 accompanied by representative of the owner. The inspection consisted of:

1. Visual inspection of the retaining structure, abutments and toe.
2. Examination of the spillway facilities, exposed portion of any outlet works and other appurtenant works.
3. Observations affecting the runoff potential of the drainage basin.
4. Evaluation of the downstream area hazard potential.

b. Dam. The dam appears to be in fair condition. From a brief survey conducted during the inspection, it was noted that the crest of the dam contained two low spots located in the center of the embankment. The crest width is seven feet. The upstream slope was measured to be 2.5H:1V and covered with hand placed riprap. In addition, the upstream slope is covered with small trees. The downstream slope was measured to be 1.5H:1V and covered with stone rubble. Portions of the downstream slope are covered with small trees. The stone rubble on the downstream slope to the left of the valve house is characterized by a longitudinal break in slope approximately 15 feet above the toe of dam. Along this lineament the stone rubble appears to be thicker than normal. It appears that the downstream slope or stone rubble may have slid at one time or additional material was added. Based on information obtained in the 1914 report in the PennDER files and observations from the visual inspection, it appears that several feet of material has been added to the crest of the dam and the spillway weir raised. The PennDER report indicates that the upstream slope, downstream slope and crest are all covered with hand placed riprap. This hand placed riprap on the crest and downstream slopes were not in evidence during the visual inspection. In addition, the walls on the valve house, located at the toe of dam, are cracked and moving.

Several seepage areas were noted during the inspection at or below the toe of dam. An extensive wet area is located at the toe of dam and was measured at a collection point to be 3 gallons per minute. Another seepage area was noted to the right of the valve house and was measured at 2 gallons per minute. A third area of seepage was located near the exit of the reservoir drain. This seepage was estimated at 2 gallons per minute and

may be a collection point for seepage exiting along the upstream wall and inside of the valve house (approximately 8 feet above the toe of dam). For location of these wet areas see page A-12.

c. Appurtenant Structures. The outlet conduit consists of 20 inch cast iron pipe which terminates in the gate house at the downstream toe of the dam. Two valves are located in the valve house to regulate the flow through the line. In the valve house the 20 inch line is diverted into two lines consisting of a 24 inch cast iron pipe and a 10 inch cast iron pipe. These two pipes discharge immediately below the valve house and into Waste House Run. The pipe is reportedly carried through the dam on a masonry wall resting on the bedrock and encased in concrete. A considerable amount of water was leaking from the valves and inside the valve house. The valves were not operated during the inspection nor have they been operated recently.

The spillway consists of an open cut located on the right abutment. The spillway weir is 34 feet long with 2:1 sideslopes. The spillway exit channel is approximately 280 feet long and consists of a stone paved open cut which is trapezoidal shaped. Some small trees and debris are located in the spillway and spillway exit channel.

d. Reservoir Area. The watershed is covered mostly with timberland. The reservoir slopes are gentle and are not susceptible to massive landslides which would affect the storage volume of the reservoir or overtopping of the dam by displacing water.

e. Downstream Channel. The downstream channel of Waste House Run No. 3 Dam is narrow and confined for the first 5000 feet downstream of the dam. Approximately 3000 feet downstream of the dam is Waste House Run No. 2 Dam. Approximately 5000 feet downstream Waste House Run passes beneath a railroad embankment and enters a strip mine area. Approximately 2 miles downstream Waste House Run passes through an extensive mining complex.

3.2 Evaluation. In general, the embankment and appurtenant structures appear to be in fair condition, but poorly maintained. Based on evidence obtained from the visual inspection and from data contained in PennDER files, it appears that the top of dam has been raised and/or modified. The downstream slope appears to be moving and has caused structural damage to the valve house. The seepage areas located at the toe of dam should be monitored at a regular basis.



SECTION 4  
OPERATIONAL PROCEDURES

4.1 Procedures. The reservoir water surface is maintained at the spillway crest elevation 1713.0. Water has not been drawn off the reservoir for several years. Excess inflow discharges over the spillway crest.

4.2 Maintenance of the Dam. No planned maintenance schedule exists. Maintenance of the dam is considered poor and is performed by the Municipal Authority's staff.

4.3 Maintenance of Operating Facilities. Maintenance of the operating facilities is considered poor. The owner's representative was unaware of the reservoir drain being operated in the past few years.

4.4 Warning System in Effect. At the time of the inspection no system was in effect to warn downstream residents of large spillway discharges or imminent failure of the dam.

4.5 Evaluation. Maintenance of the dam and operating facilities is considered poor. There is no warning system in effect to warn downstream residents.

SECTION 5  
HYDRAULICS AND HYDROLOGY

5.1 Evaluation of Features.

a. Design Data. A report prepared in 1914 by PennDER indicates that the spillway capacity is 925 cfs. Our calculations indicate that the spillway capacity is approximately 490 cfs. This reduction in the spillway capacity supports the observations that the crest of the spillway and embankment were raised at some point in time.

b. Experience Data. No rainfall, runoff or reservoir level data were available. The spillway reportedly has functioned adequately in the past.

c. Visual Observations. The spillway appears to be in fair condition, but poorly maintained. Brush and small trees growing in the spillway have been left unattended and debris is collecting in the spillway channel.

Two low spots were located in the middle of the embankment.

d. Overtopping Potential. Overtopping potential was investigated through the development of the probable maximum flood (PMF) for the watershed and the subsequent routing of the PMF and fractions of the PMF through the reservoir and spillway.

The Corps of Engineers, Baltimore District, has directed that the HEC-1 Dam Safety Version systemized computer program be utilized. The program was prepared by the Hydrologic Engineering Center (HEC), U.S. Army Corps of Engineers, Davis, California, July, 1978. The major methodologies or key input data for this program are discussed briefly in Appendix D.

5.2 Evaluation Assumptions. To enable us to complete the hydraulic and hydrologic analysis for this structure, it was necessary to make the following assumptions.

1. Initial water level before flood was at the spillway crest elevation 1713.0.

2. The top of dam was considered to be the low point of 1715.7.

5.3 Summary of Overtopping Analysis. Complete summary sheets for the computer output are presented in Appendix D.

Peak inflow (PMF)	1012 cfs
Spillway capacity	490 cfs

a. Spillway Adequacy Rating. The Spillway Design Flood (SDF) for this dam is the PMF. The SDF is based on the hazard and size classification of the dam. Based on the following definition provided by the Corps of Engineers, the spillway is rated as inadequate as a result of our hydrologic analysis.

Inadequate - All high hazard dams which do not pass the SDF (PMF), but where failure due to overtopping does not significantly increase the hazard for loss of life downstream.

The spillway and reservoir are capable of controlling approximately 55% of the PMF without overtopping the embankment. A computer printout of the hydrology is included in Appendix D.

5.4 Summary of Dam Breach Analysis. As the subject dam can satisfactorily pass 50% of the PMF without failure (based on our analyses) it was not necessary to perform a breach analysis and downstream routing of the flood wave.

SECTION 6  
STRUCTURAL STABILITY

6.1 Evaluation of Structural Stability.

a. Visual Observations. Based on the data contained in the PenNDER files and from observations from the visual inspection, it is apparent that the crest of the dam and spillway have been raised in the past. The crest of the dam and downstream slope have been modified. There is no data documenting this post construction change. It is evident that some movement of the downstream slope has taken place in the past. The lineament and thickening of the stone rubble located to the right of the valve house on the downstream slope and movement of the upstream wall of a valve house support this conclusion. The seepage areas outlined in Section 3.1b indicate a seepage rate of approximately 7 gallons per minute (at the time of inspection). The wet area located on the upstream wall of the valve house is approximately 8 feet above the toe of dam. All of these observations indicate that a stability analysis of the structure is warranted.

b. Design and Construction Data. A small amount of design data is available in the PenNDER files. However, no stability analyses have been performed.

c. Operating Records. No operating records are maintained.

d. Post Construction Changes. As outlined in Sections 3.1b and 6.1a it is obvious that some post construction changes have been made to the dam, but not documented.

e. Seismic Stability. The dam is located in seismic zone 1. No seismic stability analyses has been performed. Normally, it can be considered that if a dam in this zone is stable under static loading conditions, it can be assumed safe for any expected earthquake loading.

SECTION 7  
ASSESSMENT AND RECOMMENDATIONS/REMEDIAL MEASURES

7.1 Dam Assessment.

a. Safety. The dam appears to be in fair condition. The visual observations and hydrologic and hydraulic calculations indicate that Waste House Run No. 3 Dam's spillway is inadequate. The spillway control section has deteriorated and should be repaired. The spillway is capable of controlling approximately 55% of the PMF without overtopping the earth embankment. The significant movement of the downstream slope rubble, movement of the walls of the valve house, seepage areas, and high level of seepage on the upstream wall of the valve house indicate that a stability analyses is warranted. No stability analyses are on record for this dam.

b. Adequacy of Information. Sufficient information is available to complete a Phase I Report.

c. Urgency. The recommendations suggested below should be implemented immediately.

d. Necessity for Further Investigation. In order to accomplish some of the recommendations/remedial measures outlined below, further investigations will be required by a professional engineer knowledgeable in dam design and analysis.

7.2 Recommendations/Remedial Measures.

1. The spillway control section (weir) should be repaired.
2. A detailed study, including a stability analysis, should be conducted by a registered professional engineer knowledgeable in earth dams to evaluate the seepage, movement of the walls in the valve house and possible downstream slope instability. The study should include monitoring and testing as required.
3. All brush, trees and debris should be cleared from the spillway.
4. All brush and trees should be cleared from the slopes and crest under the direction of a professional engineer knowledgeable in the design and construction of earth dams.
5. All seepage areas should be monitored on a regular basis and after periods of heavy precipitation and evaluated by a professional engineer knowledgeable in dam design and analyses.
6. Some means of upstream positive closure of the drainline should be developed in the case of emergencies.

7. The leaking valves located in the valve house should be repaired and exercised and lubricated on a regular basis.

8. A warning system should be developed to warn downstream residents of large spillway discharges or imminent failure of the dam.

9. Regular safety inspections should be conducted in accordance with provisions stipulated by the Commonwealth of Pennsylvania regarding the inspection of dams.

10. Improve the access to the dam so the dam will be accessible during periods of flooding.

APPENDIX A  
CHECKLIST, VISUAL INSPECTION, PHASE I

CHECK LIST  
VISUAL INSPECTION  
PHASE I

NAME OF DAM Waste House No. 3 Dam COUNTY Schuylkill STATE Pennsylvania ID# PA 684  
 TYPE OF DAM Earthfill and rockfill HAZARD CATEGORY High  
 DATE(s) INSPECTION November 8 and 16, 1979 WEATHER Cloudy, warm TEMPERATURE 50°

POOL ELEVATION AT TIME OF INSPECTION 1713.0 M.S.L. TAILWATER AT TIME OF INSPECTION None. M.S.L.

INSPECTION PERSONNEL:

R. Jeffrey Kimball - L. Robert Kimball and Associates  
James T. Hockensmith - L. Robert Kimball and Associates  
O.T. McConnell - L. Robert Kimball and Associates  
 \_\_\_\_\_  
 \_\_\_\_\_

James T. Hockensmith  
 \_\_\_\_\_  
 RECORDER



# EMBANKMENT

VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS OR RECOMMENDATIONS
SURFACE CRACKS	None noted.	
UNUSUAL MOVEMENT OR CRACKING AT OR BEYOND THE TOE	There is some unusual slope movement on the downstream slope to the right of the valve house. This is evident by thickening of the stone rubble and a horizontal lineament.	
SLOUGHING OR EROSION OF EMBANKMENT AND ABUTMENT SLOPES	See above.	
VERTICAL AND HORIZONTAL ALIGNMENT OF THE CREST	Horizontal appears to be good. Vertical alignment spot. See page A-12.	low
RIPRAP FAILURES	None noted.	

# EMBANKMENT

VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS OR RECOMMENDATIONS
VEGETATION	Both the upstream and downstream slopes contain small trees.	
JUNCTION OF EMBANKMENT AND ABUTMENT, SPILLWAY AND DAM	Appears to be good.	
ANY NOTICEABLE SEEPAGE	Three seepage areas located at the toe of the dam and a wet area on the upstream wall of the house. See page A-12 for location.	valve
STAFF GAUGE AND RECORDER	None.	
DRAINS	Construction history indicates that two drains were provided to control springs located during construction. These were not evident during inspection.	

**CONCRETE/MASONRY DAMS**

<b>VISUAL EXAMINATION OF</b>	<b>OBSERVATIONS</b>	<b>REMARKS OR RECOMMENDATIONS</b>
<b>ANY NOTICEABLE SEEPAGE</b>	Not applicable.	
<b>STRUCTURE TO ABUTMENT/EMBANKMENT JUNCTIONS</b>	Not applicable.	
<b>DRAINS</b>	Not applicable.	
<b>WATER PASSAGES</b>	Not applicable.	
<b>FOUNDATION</b>	Not applicable.	

# CONCRETE/MASONRY DAMS

VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS OR RECOMMENDATIONS
SURFACE CRACKS CONCRETE SURFACES	Not applicable.	
STRUCTURAL CRACKING	Not applicable.	
VERTICAL AND HORIZONTAL ALIGNMENT	Not applicable.	
MONOLITH JOINTS	Not applicable.	
CONSTRUCTION JOINTS	Not applicable.	
STAFF GAUGE OR RECORDER	Not applicable.	

# OUTLET WORKS

VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS OR RECOMMENDATIONS
CRACKING AND SPALLING OF CONCRETE SURFACES IN OUTLET CONDUIT	Outlet pipe not observed during the inspection. The valves in the valve house were leaking.	
INTAKE STRUCTURE	Unobserved.	
OUTLET STRUCTURE	Pipes discharge directly to Waste House Run. Valve house in very deteriorated condition.	
OUTLET CHANNEL	Waste House Run.	
EMERGENCY GATE	Valve at downstream toe of dam.	

# UNGATED SPILLWAY

VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS OR RECOMMENDATIONS
CONCRETE WEIR	Deteriorated. Needs to be repaired.	
APPROACH CHANNEL	Lake.	
DISCHARGE CHANNEL	Trapezoidal shaped. Open cut with hand placed stone riprap.	
BRIDGE AND PIERS	None.	

# GATED SPILLWAY

VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS OR RECOMMENDATIONS
CONCRETE SILL	Not applicable.	
APPROACH CHANNEL	Not applicable.	
DISCHARGE CHANNEL	Not applicable.	
BRIDGE AND PIERS	Not applicable.	
GATES AND OPERATION EQUIPMENT	Not applicable.	

# DOWNSTREAM CHANNEL

VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS OR RECOMMENDATIONS
CONDITION (OBSTRUCTIONS, DEBRIS, ETC.)	Steep, narrow and confined. Approximately 3000 feet downstream is Waste House Run No. 2 Dam. Approximately 1 mile downstream is a culvert and railroad embankment.	
SLOPES	Gentle. Appear to be stable.	
APPROXIMATE NO. OF HOMES AND POPULATION	Mining complex and several dwellings, 50 people.	




# RESERVOIR


VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS OR RECOMMENDATIONS
SLOPES	Moderate. Appear to be stable.	
SEDIMENTATION	Does not appear to be excessive.	

# INSTRUMENTATION


VISUAL EXAMINATION OF		OBSERVATIONS	REMARKS OR RECOMMENDATIONS
MONUMENTATION/SURVEYS	None.		
OBSERVATION WELLS	None.		
WEIRS	None.		
PIEZOMETERS	None.		
OTHER	None.		



A-12



**SPILLWAY PROFILE**  
(Not to Scale)



**PROFILE  
LOOKING UPSTREAM**



**WASTE HOUSE RUN DAM NO. 3**  
Scale 1" = 150'

**APPENDIX B**  
**CHECKLIST, ENGINEERING DATA, DESIGN, CONSTRUCTION, OPERATION,**  
**PHASE I**

CHECK LIST  
ENGINEERING DATA  
DESIGN, CONSTRUCTION, OPERATION  
PHASE I

Waste House Run  
NAME OF DAM No. 3 Dam  
ID# PA 684

ITEM	REMARKS
AS-BUILT DRAWINGS	One drawing, poor condition showing the foundation drains collecting water from the springs.
REGIONAL VICINITY MAP	U.S.G.S. quadrangle.
CONSTRUCTION HISTORY	Brief history outlined in Pennder files. See Section 1.2g.
TYPICAL SECTIONS OF DAM	None.
OUTLETS - PLAN - DETAILS - CONSTRAINTS - DISCHARGE RATINGS RAINFALL/RESERVOIR RECORDS	None. None. None. None. None.


ITEM	REMARKS
DESIGN REPORTS	None.
GEOLOGY REPORTS	None.
DESIGN COMPUTATIONS HYDROLOGY & HYDRAULICS DAM STABILITY SEEPAGE STUDIES	None.
MATERIALS INVESTIGATIONS BORING RECORDS LABORATORY FIELD	None.
POST-CONSTRUCTION SURVEYS OF DAM	None.
BORROW SOURCES	Unknown.

ITEM	REMARKS
MONITORING SYSTEMS	None.
MODIFICATIONS	Not documented.
HIGH POOL RECORDS	None.
POST CONSTRUCTION ENGINEERING STUDIES AND REPORTS	None.
PRIOR ACCIDENTS OR FAILURE OF DAM DESCRIPTION REPORTS	Unknown.
MAINTENANCE OPERATION RECORDS	None.



ITEM	REMARKS
SPILLWAY PLAN SECTIONS DETAILS	None.
OPERATING EQUIPMENT PLANS & DETAILS	None.

**APPENDIX C**  
**PHOTOGRAPHS**



WASTE HOUSE RUN DAM NO. 3

WASTE HOUSE RUN DAM NO. 3

PHOTO INDEX

P - INDICATES PHOTO LOCATION

C-1

# WASTE HOUSE RUN NO. 3 DAM

## Photograph Descriptions

### Sheet 1. Front




- (1) Upper left - Upstream slope of dam.
- (2) Upper right - Downstream slope of dam. Valve house at toe.
- (3) Lower left - Seepage exiting downstream and to the right of valve house.
- (4) Lower right - Discharge end of blow off pipes.




### Sheet 1. Back

- (5) Upper left - Spillway discharge channel.
- (6) Upper right - Spillway weir.
- (7) Lower left - Inside valve house. Note cracks in wall and seepage.
- (8) Lower right - Downstream exposure.

TOP OF PAGE

1	2
3	4





**APPENDIX D**  
**HYDROLOGY AND HYDRAULICS**

## APPENDIX D HYDROLOGY AND HYDRAULICS

Methodology. The dam overtopping and breach analyses were accomplished using the systemized computer program HEC-1 (Dam Safety Investigation), September, 1978, prepared by the Hydrologic Engineering Center, U.S. Army Corps of Engineers, Davis, California. A brief description of the methodology used in the analysis is presented below.

1. Precipitation. The Probable Maximum Precipitation (PMP) is derived and determined from regional charts prepared from past rainfall records including "Hydrometeorological Report No. 40" prepared by the U.S. Weather Bureau.

The index rainfall is reduced from 10% to 20% depending on watershed size by utilization of what is termed the HOP Brook adjustment factor. Distribution of the total rainfall is made by the computer program using distribution methods developed by the Corps.

2. Inflow Hydrograph. The hydrologic analysis used in development of the overtopping potential is based on applying a hypothetical storm to a unit hydrograph to obtain the inflow hydrograph for reservoir routing.

The unit hydrograph is developed using the Snyder method. This method requires calculation of several key parameters. The following list gives these parameters their definition and how they were obtained for these analysis.

Parameter	Definition	Where Obtained
Ct	Coefficient representing variations of watershed	From Corps of Engineers*
L	Length of main stream channel miles	From U.S.G.S. 7.5 minute topographic
Lca	Length on main stream to centroid of watershed	From U.S.G.S. 7.5 minute topographic
Cp	Peaking coefficient	From Corps of Engineers*
A	Watershed size	From U.S.G.S. 7.5 minute topographic

\*Developed by the Corps of Engineers on a regional basis for Pennsylvania.



3. Routing. Reservoir routing is accomplished by using Modified Plus routing techniques where the flood hydrograph is routed through reservoir storage. Hydraulic capacities of the outlet works, spillways and the crest of the dam are used as outlet controls in the routing.

The hydraulic capacity of the outlet works can either be calculated and input or sufficient dimensions input and the program will calculate an elevation discharge relationship.

Storage in the pool area is defined by an area - elevation relationship from which the computer calculates storage. Surface areas are either planimetered from available mapping or U.S.G.S. 7.5 minute series topographic maps or taken from reasonably accurate design data.

4. Dam Overtopping. Using given percentages of the PMF the computer program will calculate the percentage of the PMF which can be controlled by the reservoir and spillway without the dam overtopping.

5. Dam Breach and Downstream Routing. The computer program is equipped to determine the increase in downstream flooding due to failure of the dam caused by overtopping. This is accomplished by routing both the pre-failure peak flow and the peak flow through the breach (calculated by the computer with given input assumptions) at a given point in time and determining the water depth in the downstream channel. Channel cross-sections taken from U.S.G.S. 7.5 minute topographic maps were used in the downstream flood wave routing. Pre and post failure water depths are calculated at locations where cross-sections are input.

# HYDROLOGY AND HYDRAULICS ANALYSIS DATA BASE

NAME OF DAM: Waste House Run No. 3 Dam

PROBABLE MAXIMUM PRECIPITATION (PMP) =  $22.2 (1.005) = 22.3$  inches

STATION	1	2	3
---------	---	---	---

Station Description	Waste House Run No. 3 Dam
---------------------	---------------------------

Drainage Area (square miles)	0.37
---------------------------------	------

Cumulative Drainage Area (square miles)	0.37
--	------

Adjustment of PMF for Drainage Area (%) <sup>(1)</sup>	
6 hours	117
12 hours	127
24 hours	136
48 hours	143
72 hours	145

Snyder Hydrograph	
Parameters	
Zone <sup>(2)</sup>	13
C <sub>p</sub> <sup>(3)</sup>	0.50
C <sub>t</sub> <sup>(3)</sup>	1.85
L (miles) <sup>(4)</sup>	1.0
L <sub>ca</sub> (miles) <sup>(4)</sup>	0.40
t <sub>p</sub> = C <sub>t</sub> (LxL <sub>ca</sub> ) 0.3 hrs.	1.41

Spillway Data	
Crest Length (ft)	34' bottom
Freeboard (ft)	2.7
Discharge Coefficient	C' = 0.95
Exponent	N/A

- (1) Hydrometeorological Report 40 (Figure 1), U.S. Army Corps of Engineers, 1965.
- (2) Hydrological zone defined by Corps of Engineers, Baltimore District, for determining Snyder's coefficients (C<sub>p</sub> and C<sub>t</sub>).
- (3) Snyder's Coefficients.
- (4) L=Length of longest water course from outlet to basin divide.  
L<sub>ca</sub>=Length of water course from outlet to point opposite the centroid of drainage area.

CHECK LIST  
HYDROLOGIC AND HYDRAULIC  
ENGINEERING DATA

DRAINAGE AREA CHARACTERISTICS: DA-0.37 mi<sup>2</sup> Wooded, mild slopes

ELEVATION TOP NORMAL POOL (STORAGE CAPACITY): 193 ac-ft

ELEVATION TOP FLOOD CONTROL POOL (STORAGE CAPACITY): 239 ac-ft

ELEVATION MAXIMUM DESIGN POOL: Unknown

ELEVATION TOP DAM: 1715.7

SPILLWAY CREST:

a. Elevation	<u>1713.0</u>
b. Type	<u>Trapezoidal</u>
c. Width	<u>34'</u>
d. Length	<u>Unknown</u>
e. Location Spillover	<u>Right abutment</u>
f. Number and Type of Gates	<u>None</u>

OUTLET WORKS:

a. Type	<u>20" CIP</u>
b. Location	<u>Maximum section</u>
c. Entrance inverts	<u>Unknown</u>
d. Exit inverts	<u>Approximately 1675.5'</u>
e. Emergency draindown facilities	<u>20" CIP</u>

HYDROMETEOROLOGICAL GAUGES:

a. Type	<u>None</u>
b. Location	<u>None</u>
c. Records	<u>None</u>

MAXIMUM NON-DAMAGING DISCHARGE: Unknown



L. ROBERT KIMBALL & ASSOCIATES  
CONSULTING ENGINEERS & ARCHITECTS  
EDENSBURG PENNSYLVANIA

DAM NAME WASTE HOUSE RUN No. 3

I.D. NUMBER PA. 54-26

SHEET NO. 1 OF 3

BY OTM DATE 3-12-80

### LOSS RATE AND BASE FLOW PARAMETERS

AS RECOMMENDED BY THE CORPS OF ENGINEERS,  
BALTIMORE DISTRICT.

STRTL = 1 INCH

CNSTL = 0.05 IN/HR

STR TQ = 1.5 cfs/mi<sup>2</sup>

QRCSN = 0.05 (5% OF PEAK FLOW)

RTIOR = 2.0

### ELEVATION-AREA-CAPACITY RELATIONSHIPS

FROM U.S.G.S. 7.5-MIN. QUAD., DER FILES AND  
FIELD INSPECTION DATA.

AT SPILLWAY CREST ELEVATION = 1713'

INITIAL STORAGE = 192.5 AC·FT

POND SURFACE AREA = 15.2 AC

AT ELEV. 1720, AREA = 25.3 AC.

" " 1740, AREA = 53 AC

FROM THE CONIC METHOD FOR RESERVOIR VOLUME.  
FLOOD HYDROGRAPH PACKAGE (HEC-1), DAM  
SAFETY VERSION (USER'S MANUAL).

$$H = 3V/A = 3(192.5)/15.2 = 38'$$

ELEVATION WHERE AREA EQUALS ZERO;

$$1713' - 38' = 1675'$$

AREA (AC)	0	15.2	20	30	40	53
ELEV. (FT.)	1675	1713	1716	1723	1731	1740



L. ROBERT KIMBALL & ASSOCIATES  
CONSULTING ENGINEERS & ARCHITECTS  
EBENSBURG PENNSYLVANIA


DAM NAME WASTE HOUSE RUN No. 3

I.D. NUMBER PA. 54-26

SHEET NO. 2 OF 3

BY O.T.M. DATE 3-12-80

# DISCHARGE RATING CURVE



(NOT TO SCALE)

## TRAPEZOIDAL FLOW

$B = 34'$   
 $Z = 2$   
 $C' = 0.95$   
 $h_p = \text{VARIABLE}$

## ASSUMED STANDARD WEIR FLOW

$C = 3.1$   
 $L = 44.8'$   
 $H = \text{VARIABLE}$

ELEV. (FT)	$h_p$ (FT)	$Q_1$ (cfs)	$h$ (FT)	$Q_2$ (cfs)	* $Q$ (cfs)
1713	0	0			0
1714	1	104			100
1715	2	305			300
1715.7	2.7	491			490
1716			0.3	23	510
1717			1.3	206	700
1718			2.3	484	970
1720			4.3	1238	1730
1722			6.3	2196	2690
1725			9.3	3939	4430

\*  $Q$  ROUNDED  
TO NEAREST  
10 cfs.

$$\text{WHERE: } Q = 8.03 C' h_v (h_p - h_v) [B + Z (h_p - h_v)]$$

$$h_v = 3 (2Z h_p + B) - (16 Z^2 h_p^2 + 16 Z B h_p + 9 B^2)^{1/2} / 10 Z$$

FROM: WATER & WASTEWATER ENGINEERING (11-14) & (11-15)  
BY FAIR, GEYER & OKUM 1966



L. ROBERT KIMBALL & ASSOCIATES  
CONSULTING ENGINEERS & ARCHITECTS  
EBENSBURG PENNSYLVANIA

DAM NAME WASTE HOUSE RUN No. 3

I.D. NUMBER PA. 54-26

SHEET NO. 3 OF 3

BY OTM DATE 3-12-80

OVERTOP PARAMETERS

TOP OF DAM ELEV. (LOW SPOT) = 1715.7'

LENGTH OF DAM (EXCLUDING SPILLWAY) = 1050

COEFFICIENT OF DISCHARGE = 3.0 (BROAD CREST)

\$L\_{MAX} = 1800'

\$V\_{MAX} = 1720'

\*\*\*\*\*  
 FLOOD HYDROGRAPH PACKAGE (HEC-1)  
 DAM SAFETY VERSION JULY 1978  
 LAST MODIFICATION 26 FEB 79  
 \*\*\*\*\*

ANALYSIS OF DAM OVERTOPPING USING RATIOS OF PMF									
HYDROLOGIC-HYDRAULIC ANALYSIS OF SAFETY OF WASTHOUSE RUN DAM NO. 3									
RATIOS OF PMF ROUTED THROUGH THE RESERVOIR (PA. 54-26)									
1	A1	288	0	15	0	0	0	0	0
2	A2	B1	5	1	1	1	1	1	1
3	A3	J	1	6	1	1	1	1	1
4	B	288	0	15	0	0	0	0	0
5	B1	5	1	1	1	1	1	1	1
6	J	1	6	1	1	1	1	1	1
7	J1	0.1	0.2	0.3	0.4	0.5	0.6	0.7	0.8
8	K	0	1	1	1	1	1	1	1
9	K1	0	1	1	1	1	1	1	1
10	M	1	1	0.37	1	1	1	1	1
11	P	22.3	117	127	136	143	145	1.0	0.05
12	T	1	1	1	1	1	1	1	1
13	W	1.41	0.3	1	1	1	1	1	1
14	X	1.5	0.05	2.0	1	1	1	1	1
15	K	1	2	1	1	1	1	1	1
16	K1	ROUTE	1	1	1	1	1	1	1
17	Y	1	1	1	1	1	1	1	1
18	V1	1	1	1	1	1	1	1	1
19	V4	1713	1714	1715	1716	1717	1718	1720	1725
20	V5	0	100	490	510	700	970	1730	2690
21	SA	0	15.2	20	40	53	1730	2690	4430
22	SE	1675	1713	1716	1723	1731	1740	1740	1740
23	SS	1713	1713	1716	1723	1731	1740	1740	1740
24	SD	1715.7	3.0	1.5	150	150	150	150	150
25	SL	150	320	470	1020	1300	1600	1800	1800
26	SV	1715.7	1716	1716.5	1717	1717.5	1718	1719	1720
27	K	99	1	1	1	1	1	1	1

\*\*\*\*\*  
FLOOD HYDROGRAPH PACKAGE (HEC-1)  
DAM SAFETY VERSTON JULY 1978  
LAST MODIFICATION 26 FEB 79  
\*\*\*\*\*

RUN DATE\* 80/03/05.  
TIME\* 07.18.21.

ANALYSIS OF DAM OVERTOPPING USING RATIOS OF PMF  
HYDROLOGIC-HYDRAULIC ANALYSIS OF SAFETY OF WASTHOUSE RUN DAM NO. 3  
RATIOS OF PMF ROUTED THROUGH THE RESERVOIR (PA. 54-26)

JOB SPECIFICATION											
NO	NHR	NMIN	IDAY	IHR	IMIN	METRC	IPLT	IMRT	NSTAN		
288	0	13	0	0	0	0	0	0	0		
			JOPER	NWT	LROPT	TRAPE					
			5	0	0	0					

MULTI-PLAN ANALYSES TO BE PERFORMED

RTIOS*	.10	.20	.30	.40	.50	1.00

\*\*\*\*\* SUB-AREA RUNOFF COMPUTATION \*\*\*\*\*

YNFLOW

ISTAQ	ICOMP	IECON	ITAPE	JPLT	JPRT	INAME	ISTAGE	IAUTO
1	0	0	0	0	0	J	0	0

HYDROGRAPH DATA

HYDGG	TORG	TAREA	SNAP	TRSDA	TRSPC	RATIO	ISHOW	ISAME	LOCAL
1	1	.37	0.00	.37	0.00	0.000	0	1	0

PRECIP DATA

SPFE	PMS	R6	R12	R24	R48	R72	R96
0.00	22.30	117.00	127.00	136.00	143.00	145.00	0.00

TRSPC COMPUTED BY THE PROGRAM IS .800

LOSS DATA

LROPT	STKR	DLTKR	RTIOL	ERAIN	STKRS	RTIOK	STRTL	CNSTL	ALSMX	RTIMP
0	0.00	0.00	1.00	0.00	0.00	1.00	1.00	.05	0.00	0.00





\*\*\*\*\*

# HYDROGRAPH ROUTING

## ROUTE

ISIAO ICOMP IECON ITAPE JPLI JPRT INAME ISTAGE IAUO

ROUTING DATA

LAG ARSKC K ISK STORA ISPRAT

STAGE 1713.00 1715.00 1715.70 1716.00 1717.00 1718.00 1720.00 1722.00

171725.00

FLOW 0.00 100.00 300.00 490.00 510.00 700.00 970.00 1730.00 2690.00

4430.00

SURFACE AREA# 0. 15. 20. 30. 40. 53.

CAPACITY# 0. 193. 245. 419. 698. 1115.

ELEVATION# 1675. 1713. 1716. 1723. 1731. 1740.

CREL SPWD COW EXPW ELEV COOL CAREA EXPL

1713.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0

TOPEL COOD EXPO DAMWID

1715.7 3.0 1.5 150.

CREST LENGTH 150. 320. 470. 1020. 1300. 1500. 1600. 1800.

AT OR BELOW

ELEVATION 1715.7 1716.0 1716.5 1717.0 1717.5 1718.0 1719.0 1720.0

PLAK FLOW AND STORAGE (END OF PERIOD) SUMMARY FOR MULTIPLE PLAN-RATIO ECONOMIC COMPUTATIONS  
 FLOWS IN CUBIC FEET PER SECOND (CUBIC METERS PER SECOND)  
 AREA IN SQUARE MILES (SQUARE KILOMETERS)


OPERATION	STATION	AREA	PLAN	RATIOS APPLIED TO FLOWS					
				RATIO 1	RATIO 2	RATIO 3	RATIO 4	RATIO 5	RATIO 6
				.10	.20	.30	.40	.50	1.00
HYDROGRAPH AT	1	.37 .961	1	101.	202.	304.	405.	506.	1012.
				2.8711	5.7311	8.6011	11.4611	14.3311	28.6611
ROUTED TO	2	.37 .961	1	74.	164.	253.	345.	438.	996.
				2.3311	4.8511	7.3711	9.7711	12.4111	26.2111

6/6

SUMMARY OF DAM SAFETY ANALYSIS

PLAN 1 .....									
ELEVATION		INITIAL VALUE		SPILLWAY CREST		TOP OF DAM			
STORAGE		1713.00		1713.00		1715.70			
OUTFLOW		193.		193.		239.			
		0.		0.		490.			
RATIO OF PPR	MAXIMUM RESERVOIR W.S.ELEV	MAXIMUM DEPTH OVER DAM	MAXIMUM STORAGE AC-FT	MAXIMUM OUTFLOW CFS	DURATION OVER TOP HOURS	TIME OF		TIME OF	
						MAX OUTFLOW		FAILURE	
						HOURS		HOURS	
.10	1713.74	0.00	204.	74.	0.00	42.75	0.00	0.00	0.00
.20	1714.32	0.00	214.	164.	0.00	42.25	0.00	0.00	0.00
.30	1714.77	0.00	222.	253.	0.00	42.25	0.00	0.00	0.00
.40	1715.17	0.00	229.	345.	0.00	42.00	0.00	0.00	0.00
.50	1715.51	0.00	236.	432.	0.00	42.00	0.00	0.00	0.00
1.00	1716.33	.63	252.	996.	4.25	41.25	0.00	0.00	0.00

**APPENDIX E**  
**DRAWINGS**



WASTE HOUSE RUN RESERVOIR NO. 3

DOWN STREAM EXPOSURE MAP

SCALE 1" = 2000'

L. ROBERT KIMBALL & ASSOCIATES  
CONSULTING ENGINEERS & ARCHITECTS


E-1

**APPENDIX F**  
**GEOLOGY**

### General Geology

The Waste House Run No. 3 Dam is located in the Appalachian Mountain section of the Valley and Ridge Physiographic Province. This area is characterized by tightly folded synclines and anticlines. The bedrock underlying the dam and reservoir is the Pennsylvanian-aged Pottsville Group. This formation consist of interbedded sandstone and conglomerate, medium to coarse grained; with some coal and dark shale. The bedding is usually moderately-well developed. Joints are fairly regular, abundant and steeply dipping. The rocks comprising this formation are moderately resistant to weathering and form a good foundation for heavy structures if excavated to sound material. Care should be taken where coal has been mined. Some faulting is evidenced approximately two or three miles southeast and southwest of the reservoir.





GEOLOGIC MAP OF THE AREA AROUND SHENANDOAH CREEK, MAHANOEY TOWNSHIP DAM NO. 2 AND WASTE HOUSE RUN NO. 3 RESERVOIRS



**Pottsville Group**

Light gray to white, coarse grained sandstone and conglomerates with some micaceous coal. Includes Sharp, Mountain, Schuylkill, and Tumbling Run Formations.

Scale 1 : 250,000